

Madison, Wisconsin

INDEX OF SHEETS - STREETS

| SHEET NO. SHEET NO. | - | TITLE NOTES AND DETAILS |
|------------------------|---|-------------------------------|
| SHEET NO. SHEET NO. | | PLUTO STREET O.L. 13 ALLEY |

INDEX OF SHEETS - UTILITIES

| SHEET NO. | U1-U2 | PLUTO STREET SEWERS |
|-----------|-------|---------------------|
| SHEET NO. | U3 | STORM SEWER SCHEDUL |
| SHEET NO. | WI-W2 | PLUTO STREET WATER |
| SHEET NO. | W3 | WATER IMPACT PLAN |
| SHEET NO. | W4 | WATER MATERIAL LIST |

CITY OF MADISON

CITY ENGINEERING DIVISION
DEPARTMENT OF PUBLIC WORKS
PLAN OF PROPOSED IMPROVEMENT


GRANDVIEW COMMONS

PHASE 18

PLUTO STREET AND O.L. 13 ALLEY

CITY PROJECT NO. 53B2351

CONTRACT NO. 2351



PUBLIC IMPROVEMENT PROJECT APPROVED MAY 21, 2013 BY THE COMMON COUNCIL OF MADISON, WISCONSIN PUBLIC IMPROVEMENT DESIGN APPROVED BY:

THE LOCATION AND INFORMATION FOR PROPOSED NEW TREES, IN THE PUBLIC RIGHT OF WAY OR ON PUBLIC LANDS ARE APPROXIMATE AND ARE SHOWN FOR REFERENCE ONLY. THE LOCATIONS, SPECIFICATIONS AND PLANTING METHODS OF ALL PROPOSED NEW OR REPLACEMENT TREES IN THE PUBLIC RIGHT OF WAY OR ON PUBLIC LANDS SHALL BE APPROVED BY THE CITY FORESTER PRIOR TO INSTALLATION.

NO TREES IN THE RIGHT OF WAY OR ON PUBLIC LANDS SHALL BE TRIMMED, PRUNED, REMOVED OR ADVERSELY AFFECTED IN ANY WAY UNTIL THE DEVELOPER HAS RECEIVED WRITTEN PERMISSION FROM THE CITY ENGINEER OR CITY FORESTER. SAID WRITTEN PERMISSION SHALL INCLUDE LANGUAGE INDICATING THAT SECTION 10.101 OF THE MADISON GENERAL ORDINANCES AND ADMINISTRATIVE PROCEDURE MEMORANDUM NO. 6–2, REFERING TO NOTIFICATION OF PROPERTY OCCUPANTS ANDOR OWNERS, HAS BEEN COMPLIED WITH.

ALL PAVEMENT SHALL BE TYPE "A" PER STANDARD DETAIL DRAWING 4.02.

ALL ISLANDS SHALL HAVE TYPE "E" C & G PER S.D.D. 3.08 AND MOUNTABLE NOSES PER S.D.D. 3.13. ALL OTHER C & G SHALL BE TYPE "A" PER S.D.D. 3.06.

ISLAND INTERIORS SHALL BE OF SOD WHERE THE BACK TO BACK OF CURB DIMENSION IS GREATER THAN 6'.

UNDERDRAINS SHALL BE INSTALLED, PER STANDARD DETAIL DRAWING 4.05, ON PAGE 2 OF THESE PLANS, FOR 75'ON EACH SIDE OF THE LOW POINT, OR TO THE NEAREST CURB HIGH POINT. ALL UNDERDRAIN SHALL BE WRAPPED.

ALL GUTTERS SHALL DRAIN WITH A MINIMUM GRADES OF 0.5% TOWARD STORM SEWER INLETS.

PAVEMENT CROSS SLOPES SHALL BE 2%, TERRACES SHALL SLOPE AT A 4% GRADE TOWARD THE GUTTER, SHOULDERS SHALL HAVE A 4% CROSS SLOPE AND CROSS SLOPES FORMING DITCHES SHALL NOT EXCEED 4.00:1 UNLESS OTHERWISE INDICATED.

THE CROSS SLOPE OF SIDEWALKS AND BARRIER FREE SIDEWALK CURB RAMPS SHALL BE 2%. THE LONGITUDINAL GRADE OF BARRIER FREE SIDEWALK CURB RAMPS SHALL NOT EXCEED 8.33%. ALL SIDEWALK RAMPS SHALL BE CONSTRUCTED ACCORDING TO S.D.D. 3.03. AT ALL OTHER LOCATIONS THE LONGITUDINAL GRADE OF SIDEWALKS SHALL NOT EXCEED 5.0 % OR THE ADJACENT STREET GRADE WHICHEVER IS GREATER NOR BE LESS THAN 0.5% AND SHALL DRAIN TOWARD STORM SEWER INLETS. A 2 FOOT WIDE CONSRETE FLUME SHALL BE INSTALLED BETWEEN THE SIDEWALK AND THE BACK OF CURB AT SIDEWALK LOW POINTS WHICH CANNOT OTHERWISE BE DRAINED DIRECTLY TO THE GUTTER. SIDE SLOPES WITHIN TEN FEET OF A PUBLIC SIDEWALK SHALL NOT EXCEED 4.00:1. THE DESIGN OF SIDEWALK ELEVATIONS AND GRADES IS NOT INCLUDED IN THIS PLAN. ALL SIDEWALK AND SIDEWALK RAMP ELEVATIONS AND GRADES SHALL BE FIELD VERIFIED AND SET TO COMPLY WITH THE CITY OF MADISON STANDARD SPECIFICATIONS AND THE A.D.A. GUIDELINES.

OBTAIN A PRINT OUT OF THE ALIGNMENT FROM THE CITY ENGINEER PRIOR TO STAKING THIS PROJECT.

CURB STATION AND OFFSETS SHALL BE TO THE FACE OF CURB UNLESS OTHERWISE INDICATED. CURB ELEVATIONS SHALL BE TO THE TOP OF CURB (OR EXTENDED TOP OF CURB FOR DRIVEWAYS OR RAMPS) UNLESS OTHERWISE INDICATED.

POWER POLES AND OTHER OBSTRUCTIONS SHALL BE MOVED TO PROVIDE 2 FEET MINIMUM OF CLEAR DISTANCE FROM ANY FACE OF CURB OR EDGE OF SIDEWALK.

ANY INFORMATION SHOWN ON THIS PLAN, WHICH IS NOT PART OF THIS PROJECT, IS PRELIMINARY AND NOT FOR CONSTRUCTION.

THERE MAY BE EXISTING UTILITIES OR OTHER FEATURES WHICH ARE EITHER NOT SHOWN OR SHOWN INCORRECTLY ON THIS PLAN. IT IS THE RESPONSIBILITY OF THE DEVELOPER TO LOCATE AND IDENTIFY ALL UTILITIES AND TOPOGRAPHY WHICH MAY AFFECT THE CONSTRUCTION OF THESE IMPROVEMENTS.

ALL PERMANENT SIGNING AND POSTING WILL BE DETERMINED AND PROVIDED BY THE TRAFFIC ENGINEERING DIVISION, FOLLOWING CONSTRUCTION OF THESE IMPROVEMENTS.

THE DEVELOPER SHALL PROVIDE, INSTALL AND MAINTAIN ALL STREET END BARRICADES, SIGNING AND TRAFFIC CONTROL, AS REQUIRED BY THE CITY TRAFFIC ENGINEER.

PAVEMENT SAWCUTS SHALL BE AS DIRECTED BY THE CITY CONSTRUCTION ENGINEER. SAWCUTS SHOWN ON THE PLAN ARE APPROXIMATE.

CURB ON CUL DE SACS SHALL BE INSTALLED ACCORDING TO SDD 3.05.

GRANDVIEW COMMONS PHASE 18
PROJECT NO.53B2351

SHEET NO.

DETAILS

STANDARD NOTES AND COMMENTS

CITY OF MADISON


FILE NAME: M: \DESIGN\STREETS\DGN\53B2351\DETAILS\D1_NOTES.DGN

DATE: 7/2/2013

DETAILS

TYPICAL SECTIONS CITY OF MADISON

TYPICAL SECTION - PLUTO STREET




NOTES:

- * A PAVEMENT DESIGN IN ACCORDANCE WITH STANDARD DETAIL DRAWING 4.06 IS REQUIRED ON ALL PROJECTS
- **3" OF CRUSHED AGGREGATE BASE COURSE GRADATION 3
 SHALL BE PLACED UNDER THE SIDEWALK WHERE THE
 CENTERLINE GRADE OF THE STREET EXCEEDS 5%

*CITY OF MADISON MINIMUM PAVEMENT DESIGN

| TYPE | CRUSHED AGGREGATE BASE COURSE | | | ASPHALTIC CONCRETE PAVEMENT | | | |
|------|-------------------------------|-------------|-------|-----------------------------|-------------|-----------|--|
| | LOWER LAYER UPPER LAYER | | LOW | ER LAYER | UPPER LAYER | | |
| | GRADATION 1 | GRADATION 2 | TYPE | THICKNESS | TYPE | THICKNESS | |
| Α | 6" | 4 " | E-0.3 | 1.75" | E-0.3 | 1.75 " | |
| В | 6" | 4 " | E-1 | 2.5" | E-1 | 1.75 " | |
| С | 6" | 4″ | E-3 | 3.50" | E-3 | 1.75 " | |





* SEE ARROWS ON PLAN PAVEMENT FOR DIRECTION OF CROSS SLOPE.


CURBS SHALL HAVE A MINIMUM 0.5% LONGITUDINAL GRADE TOWARD INLETS.

ALL STORM WATER SHALL BE COLLECTED BY STORM SEWER INLETS PRIOR TO FLOWING OVER PRIVATE PROPERTY OR SIDEWALKS.

HORIZONTAL ALIGNMENT NOTE
EDGE OF PAVEMENT RADII SHALL
NOT BE LESS THAN 25 FEET

THE EDGE OF ALLEY PAVEMENT SHALL NOT BE CLOSER THAN 7.0' TO THE PROPERTY LINE AT ANY POINT.

UNDERDRAIN INSTALLATION



TOF GUTTER

* THE NEAR CORNER OF THE LANDING SHALL BE 5.85' FROM THE FACE OF CURB, UNLESS SPECIFIED OTHERWISE ON THE PLAN, BOTH OPPOSITE CORNERS OF THE LANDING SHALL BE LOCATED ON THE FACE OF CURB RADIUS LINE WHICH PASSES THROUGH THE MIDPOINT OF THE CURB CURVATURE.

LONGITUDINAL RAMP GRADES SHALL NOT EXCEED 1"/12" NOR BE LESS THAN 2.0% AT ANY POINT. THIS NOTE SHALL TAKE PRECEDENCE OVER ANY ELEVATION OR GRADE INDICATED ON THE PLAN.

SHEET NO.

D-3


CITY OF MADISON


GRANDVIEW COMMONS PH. 18 PROJECT NO. 53B235I


DETAILS

SIDEWALK

SIDEWALK LONGITUDINAL GRADES AT ALL LOCATIONS OTHER THAN RAMPS AND WHERE STREET GRADES ARE MORE THAN 5.0% SHALL NOT EXCEED 5.0%. WHERE STREET GRADES EXCEED 5.0%, THE SIDEWALK LONGITUDINAL GRADE SHALL NOT EXCEED THE STREET GRADE.







STRUCTURES

ALIGNMENT CODES:

'PS' = PLUTO STREET 'OL' = OUTLOT 13 GRANDVIEW COMMONS, PH. 18
PROJECT NO. 53B2351

TYPE

RCP

RCP

RCP

RCP

RCP

NOTES

SHEET NO. U-3

CITY OF MADISON

STORM SEWER SCHEDULE

(DNSTM)

TO

S-1

S-2

S-3

S-4

(UPSTM)

LGTH

(FT)

65

102

103

66

14

DISCH.

968.05

971.01

972.20

972.96

973.29

E.I.

INLET

971.01

972.20

972.71

973.29

973.36

E.I.

SLOPE

4.55%

1.17%

0.50%

0.50%

0.50%

(%)

PIPE

SIZE

15"

15"

15"

12"

12"

FROM

S-0

S-1

S-2

S-3

S-4

PIPES

P-1

P-2

P-3

P-4

P-5

| STRUC NO. | . STATION | LOCATION (OFFSET) | TYPE | TOP OF CASTING | E.I. | DEPTH | NOTES |
|--------------|--------------|----------------------|-----------------|-------------------|--------|-------|------------------------------|
| S-0 | 17'PS'+67.00 | LT-17.11 | CONCRETE COLLAR | - | 968.05 | - | - |
| S-1 | 17'PS'+00.00 | LT-15.50 | H INLET | 974.76 | 971.01 | 3.75 | FP; W/R-3067-V |
| S-2 | 15'PS'+96.00 | LT-15.50 | H INLET | 976.76 | 972.20 | 4.56 | FP; W/R-3067-V |
| S-3 | 14'PS'+91.00 | LT-15.50 | H INLET | 976.88 | 972.71 | 4.17 | FP; W/R-3067-V |
| S-4 | 15'OL'+28.53 | RT-6.75 | H INLET | 976.93 | 973.29 | 3.64 | LP, W/R-3382, SEE SDD 5.7.33 |
| S-5 | 15'OL'+28.53 | LT-6.75 | H INLET | 976.69 | 973.36 | 3.33 | LP, W/R-3382, SEE SDD 5.7.33 |


STANDARD NOTES:

- ABBREVIATIONS: AE = APRON ENDWALL; RCP = REINFORCED CONCRETE PIPE; HERCP = HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE; DNA = DOES NOT APPLY; SAS = SEWER ACCESS STRUCTURE; LP = LOW POINT INLET STRUCTURE; FP = FIELD POURED STRUCTURE; TR = TOP OF CONCRETE ROOF; NCM = NO CROWN MATCH FOR PIPES
- APPROXIMATE DISCHARGE E.I. GIVEN, ADJUST E.I. AND PIPE SLOPE IN THE FIELD.
- TOP OF CASTING GRADE GIVEN IS THE TOP OF CURB FOR INLET STRUCTURES AND THE FLOWLINE OF THE CLOSED CASTING FOR SAS's.
- TOP OF CONCRETE ROOF (TR) IS 1.25' BELOW TOP OF CASTING UNLESS OTHERWISE NOTED.
- ALL REINFORCED CONCRETE PIPES TO BE CLASS III UNLESS OTHERWISE NOTED.
- SURVEYOR TO CONFIRM THAT ALL INLET STATION / OFFSETS LINE UP WITH PROPOSED CURB AND GUTTER.
- ALL STRUCTURES CALLED OUT AS FIELD POURED SHALL BE FIELD POURED. ALL OTHER STRUCTURES (NOT INDICATED AS FIELD POURED) SHALL BE SUBMITTED TO CITY ENGINEERING FOR APPROVAL IF PRECAST STRUCTURES ARE PREFERRED. CONTACT ELIA E ACOSTA OF CITY ENGINEERING AT (608) 266-4096 FOR PRECAST APPROVALS, OR FAX SHOP DRAWINGS TO (608) 264-9275.

SPECIFIC NOTES

FILE NAME: M:\DESIGN\STREETS\DGN\53B2351\UTILITIES\STORM SCHEDULE GVC 18.XLS

DATE: 06/27/2013





- 3. MINIMIZE DISTRUPTION OF SERVICE TO EXISTING CUSTOMERS. NOTIFY PER CONTRACT REQUIREMENTS OF ANY PLANNED WATER OUTAGE.
- 4. EXISTING WATER MAIN SHALL REMAIN IN SERVICE UNTIL NEW WATER MAIN IS TESTED AND ACCEPTED BY MADISON WATER UTILITY AND ALL SERVICES ARE RECONNECTED.
- THE EXISTING UTILITIES SHOWN ON THIS PLAN REPRESENT THE BEST INFORMATION AVAILABLE TO THE WATER UTILITY AT THE TIME OF PLAN PREPARATION. CONTRACTOR IS RESPONSIBLE FOR HAVING EACH UTILITY LOCATED PRIOR TO COMMENCING WORK.

- WN1 REPLACE THE EXISTING LEAD SERVICE WITH A NEW COPPER SERVICE.
- WN2 EXTEND AND RECONNECT THE EXISTING COPPER SERVICE TO THE NEW WATER MAIN.
- WN3 EXISTING SERVICE TO BE ABANDONED WHEN THE WATER MAIN IS CUT OFF.
- WN4 DISCONNECT FROM THE OLD WATER MAIN AND RECONNECT THE EXISTING COPPER WATER SERVICE LATERAL TO THE NEW WATER MAIN.
- WN5 RELOCATE THE EXISTING FIRE HYDRANT.
- WN6 ABANDON WATER VALVE ACCESS STRUCTURE.
- $\ensuremath{\mathsf{WN7}}$ Furnish and install the new top section for the water access structure.
- WN8 ABANDON THE VALVE BOX.
- WN9 FURNISH THE DITCH, COMPACTION, AND ALL MATERIALS AND LABOR FOR THE INSTALLATION OF NEW SERVICE LATERAL.
- WN10 REMOVE AND SALVAGE EXISTING HYDRANT
- WN11 REPLACE THE EXISTING COPPER SERVICE WITH A COPPER SERVICE
- WN20+ SEE WATER IMPACT PLAN FOR CONNECTION POINT ISOLATION AND WATER SHUT-OFF NOTFICATION INFORMATION.

ESTIMATE OF MATERIALS SUPPLIED BY CONTRACTOR:

 ESTIMATE OF MATERIALS IS FOR INFORMATION ONLY. ENGINEER DOES NOT GUARANTEE ACCURACY OF MATERIAL TAKE-OFF.

10-FT - 6-IN PIPE 620-FT - 8-IN PIPE

700-FT - POLYWRAP

4 - 8-IN VALVE AND BOX

8-FT 2-IN STYROFOAM

1-IN COPPER (AS RQ'D)

REUSED MATERIALS:

1 - 5-IN HYDRANT 1 - 8-IN X 6-IN TEE

SALVAGED MATERIALS:

1 - 5-IN HYDRANT



TO OBTAIN LOCATION OF PARTICIPANTS' UNDERGROUND FACILITIES BEFORE YOU DIG IN WISCONSIN

CALL DIGGERS HOTLINE

811


or 1-800-242-8511

TOLL FREE

FAX-A-LOCATE 1-800-338-3860

TDD (FOR HEARING IMPAIRED) 1-800-542-2289

WIS. STATUTE 182,0175 (1974) REQUIRES MIN. OF 3 WORK DAYS NOTICE BEFORE YOU EXCAVATE.



W-4

SHEET NO.

WATER ESTIMATE OF MATERIALS

GRANDVIEW COMMONS PH 18 CITY OF MADISOI

PM: DENNIS CAWLEY DESIGNER: KBM

